

Thermofoil Modular Wall Panels



Description:

Transforma provides a modular wall panel system designed and manufactured for specific use in operation rooms and other areas in hospitals; the panels are manufactured with high precision using MDF covered with thermofoil (PVC sheet) through thermoforming process.

The solution is available with a normal thermofoil finish in different colors and texture, and it is also available in antimicrobial thermofoil finish in different colors and textures.

Dimensions	
Panel Width	Max. 1,100 mm
Panel Height	Max. 2,500 mm
Panel Thickness	14 mm and 20 mm

Technical Data	
Panel Composition	350 Micron polymer foil
	12mm or 18mm thick Medium Density Fiberboard (MDF)
	1 mm thick Galvanized Steel fixture supports attached to MDF

Surface finish options	Normal Thermofoil cover in different colors and textures
	Antimicrobial Thermofoil cover in different colors and textures
Fixture method	Screws on Galvanized Steel supporting structure
Fixture covering	Silicone gasket
Origin	Italy

Standards & Certification:

- Passed water immersion test for 24 hours with no anomalies or issues
- Produced under the following standards:
 - o 93/41/CEE
 - o CEI UNI EN 60601-2-52
 - o IEC 60601-2-52:2009/AMD1:2015
 - o 2011/65/UE
 - o 2006/42/CE
 - o 2006/95/CE
 - o 2004/108/CE